G. R. S. 59] (GPB - 15,000 - 20 12 13

GENERAL AND REVENUE SECRETARIAT.

1899-1900

~~191~~.

( Ganjam )

**File No.** 13 Section III

**Serial Nos.** 1-4.

# Papers Filed.

*Month*_____

SUBJECT.

Sanctions an estimate for repairing the Compound Wall &c of the Sri Gavi Gangadha Reswara Swami Temple at Ganjam.

| PREVIOUS REFERENCES. | LATER REFERENCES. |
|---|---|

SC/

Order

No. 1182 dt 29-5-97

En/

The accompanying estimate for Rs 200-0-0 to repair the compound wall of the ~~Sri~~ Gangatharaswaraswamy temple and ~~repairing~~ the verandah of Bhavajee mantap opposite the temple, at Gavipur, which has been prepared after a personal inspection of the places by the Muzrai Superintendent, is sanctioned, the charge being met from the State-Grant of Rs 15000 sanctioned in Govt Pro No. 609 Muz 7 105-92 dated 3rd Feb 96, for the repairs of Muzrai Buildings in the Province during the year 1896-7.

2 The amount sanctioned in the foregoing para will be paid on presentation to the Compr of a bill duly signed by the Muzrai Superintendent

Muzrai Secretary.

To,
The Compr to Govt

Measurement of work done in repairing the compound wall of the Sree Ganga thareswara Swami temple at Gavipur, and shifting the Verandah of Bhavaje Mantap in front of the temple.

| Details | No. | Measurement | | | Contents | Total |
|---|---|---|---|---|---|---|
| Dismantling the compound wall | 1 | 27 | 1 | 5 | 135 | |
| — Do — | 1 | 10 | 1 | 4 | 40 | |
| Total c ft | | | | | | 175 |
| Constructing compound wall newly. | 1 | 12½ | 1 | 7 | 67 | |
| Total c ft | | | | | | 67 |
| (Earthwork) Levelling the compound | 1 | 30 | 28 | 2 | 1680 | |
| Total c ft | | | | | | 1680 |
| Constructing new wall like a trial. | 1 | 60 | . | 2¼ | 135 | |
| Total c ft | | | | | | 135 |
| Dismantling the old trials. | No | | | | | 2 |
| Dismantling the Verandah including rafters, rafters &c. | 1 | 44 | 11 | . | 484 | |
| Total sft | | | | | | 484 |
| (Earthwork) Excavating the trial and removing the Stones & gravel, including the forming the ground. | 1 | 46 | 14 | 4 | 2576 | |
| — Do — | 1 | 50 | 10 | 2 | 1000 | |
| Total c ft | | | | | | 3576 |
| Constructing a Stone trial. | 1 | 60 | 1½ | 4 | 280 | |
| Total c ft | | | | | | 280 |

| | | | | | | |
|---|---|---|---|---|---|---|
| Fixing pillars for the construction of new Verandah | Total No | | | | | 4 |
| Putting Rafters reepers and tiles with new nails &c | 1 | 2 | 11 | - | 23 | |
| | Total Sft | | | | | 23, |
| Putting a new door after dismantling & complete. | 1 | 5 3/4 | 2 1/2 | - | 14 | |
| | Total Sft | | | | | 14 |
| Dismantling & removing the Anjeenya Swami temple at Sandal Koti | L.S. | | | | | 50 |
| Potty Repairs | | L.S. | | | | 10 12/16 |
| Flooring the compound with Stones. | | 60 | 30 | - | 1800 | 1800 |
| Site clearing & pointing &c | L.S. | Rupees | | | | 24 |

Abstract Measurement of work done in repairing the Compound wall ~~Abstract of Estimate for~~ of the Sree Gangatthereswara Swamy temple and shifting the Verandah of Bhavaji Mantap opposite the temple at Gavipur.

| Particulars, | Per. | Rate. | Quantity. | Cost. |
|---|---|---|---|---|
| | | Rs | | Rs. A. P. |
| Repairs to temple Compound wall | cft | | | |
| Dismantling the — do — | cft. | - 6 | 175 | 5 7 6 |
| Constructing Compound wall | cft. | - 1 | 67 | 4 3 . |
| artwork Levelling — do — only | cft. | - 1 | 1680 | 8 12 . |
| Constructing a Stone wall — do — | cft | - 1 | 135 | 8 7 . |
| Dismantling the old Pials | each | 5 | 2 | 10 . . |
| Flooring with old stone slabs | Sqr. | 3 8 | 16.00 | 56 . . |
| Site clearing & forming the ground outside the Compound | Lumpk | Sum Rs | | 15 - - |
| Shifting the Verandah Bhavaji Mantap | | | | |
| Dismantling the Verandah | Sft. | - 2 | 4824 | 5 . 8. |
| Earth & Stone work) Dismantling and removing the Pials including forming &c | cgd. | - 4 | 132½ | 33 2 . |
| Constructing a stone Pial to support the building | cft. | - 1 | 280 | 17 8 . |
| Fixing pillars for Verandah | each | - 12 | 4 | 3 . . |
| Putting Rafters, Reepers &c with new bolts nails &c. | Sqr | 6 | 2.31 | 13 13 10 |
| Putting a new door | Sft. | - 8 | 14 | 7 - - |
| Petty Repairs such as forming the ground inside, closing up the holes &c. including pointing &c. | Lumpk | Sum | | 12 10 - 13 - - |
| Total Rupees | | | | ~~203 6 -~~ Bl. 200 0 0 |

25/8/97

Sanctioned for Rs.

No. dated

Bulaboiste... Co.

in ~~Govt.~~ Pres.

Sl. 2

*Proceedings of the Government of Mysore.*

READ:—

Government Proceedings No. 1182 dated 29th May 1897 sanctioning an estimate amounting to Rs 200 — — — for repairing the Compound wall of the Sri Gavi Gangadhareswara ~~Temp~~ Swami Temple at Gavipur and also removing the verandah of Bhavajee Mantap opposite the temple.

ORDER THEREON.—No. 301 En 2

*Dated Bangalore,* 1st September 1897

A bill for Rs 200 — — being the actual cost of ~~work done to~~ completing the aforesaid work ~~up to~~ ~~180~~ is countersigned and forwarded to the Comptroller for audit and return to this office for payment.

2. A copy of the Measurement list on which the bill is based is also forwarded to the Comptroller for reference.

*Main Secretary.*

To The Comptroller to the Government of Mysore with the bill and a copy of the Measurement Abstract

Balakrishnaiah

....Government of Mysore.....Dr.

| Particulars. | Amount. | Remarks. |
|---|---|---|
| The actual cost of repairing compound wall of the the Gangatheeswara Swami temple at Gavipur and also removing the ~~Bhoo~~ Verandah of ~~the~~ Bhavaji Mantap opposite the temple. | 200 | Vide Govt Pro No 1182 dated 29-6-97 |
| To be made payable at the State Huzur Treasury | 200 | |

Huzur Superintendent.

Balakrishnaiah

Pl 4

15/9/97

మీ కోసం రు/- నిం॥ధ్యేయ మనుజరం
లు మూవీ రింటేంటేంటు రవరళ్ళిసిని.

బేంగళూరు తప్పక పోలీసులు శ్రీరు
వవర్ధరులాశిగనమగ రంట్రాక్టర్
తిమ్మాలుబ్బరు శరశి శేరుంట్ల శశిశి.

బేంగళూరు గరిపురద గంశాం
ధరస్థాపిలు వర దేవస్థానవళ్ళిశేల
రటిటరిడీరి మూరి [illegible] స్థాపి
సోంశ్రిద మఱుంరి మోంగలగి సోంస్థర
రు ఉట్టిద 13రి శెప్టెంబర్ 1897రిల్లు రి
(200) లుబ్బారు రు పాయిగళ భాశెల
రు మూరుత్రిజరిలుల్లి ఉణతేగవరు శేరుం
శ్రీ వంశే నవుంరాంద విల్లు లుం రిశ
శ్రీ
రర్శవశెస్థే సంపు లురుత్తే లు దుశి
పాయి లుం సంద భక్తరల్లి నగిసే
లుబ్బరు శరరశ్రీ న్యరువదిల్లవేంశ
శరశి శేరుంట్ల శశిశి

15/9/97
బేంగళూరు స్థాంటేగళు
B. Hanumiah
Balakrishna Rao

ఏ.ఎం.ఎస్. పాంర్
తిమ్మాలుబ్బర
గుత్తేదారుడు